



Kenton C. Ward, CFM Surveyor of Hamilton County Phone (317) 776-8495 Fax (317) 776-9628 Suite 188 One Hamilton County Square Noblesville, Indiana 46060-2230

March 24, 2011

To: Hamilton County Drainage Board

Re: Stony Creek / Locke Arm, 191<sup>st</sup> Street to 196<sup>th</sup> Street Reconstruction

The Hamilton County Drainage Board held a public hearing on May 24<sup>th</sup>, 2010 regarding a proposed reconstruction project known as the Stony Creek Drain / Locke Arm. (See Drainage Board Meeting Minutes, Book 12, pages 568 – 586) The original hearing on May 24<sup>th</sup>, 2010, indicated an estimated cost of \$1,372,295.00. The Hamilton County Drainage Board continued the hearing until July 26<sup>th</sup>, 2010.

At the July 26<sup>th</sup> 2010 Drainage Board meeting six (6) options were presented. Option #6 was approved with an estimated cost of \$556,151.50. (See Drainage Board Meeting Minutes, Book 13, pages 76-81) The reconstruction assessments were reduced to the revised cost estimate. Assessments under \$100 have been certified to start collections in 2011. Assessments over \$100 have been split and the first half will start collections in 2011 and the second half will start collections in 2012.

Option #6 reconstructed the Stony Creek / Locke Arm from 196<sup>th</sup> Street to 211<sup>th</sup> Street. The project included dredging, tree removal on the operational side, sediment basins, pipe outlets, rip rap bank protection and seeding of the channel slopes and filter strips. This project is under construction and is 96 % complete on the clearing and 50% complete on the dredging.

It now appears there may be funds available to do additional work in the watershed to further improve drainage. It is best to do additional work on this channel while the contractor is in place, which will not incur additional mobilization costs.

## Proposed extension of the Reconstruction Project from 191<sup>st</sup> to 196<sup>th</sup> Street

Several landowners within the Stony Creek / Locke Arm watershed appeared before the Drainage Board at the February 14, 2011 Drainage Board Meeting requesting additional work to be performed on the Stony Creek / Locke Arm, south of the approved reconstruction project. The landowners stated that the approved Stony Creek / Locke Arm reconstruction would be less effective at draining the watershed if there were remaining flow line obstructions south of 196<sup>th</sup> Street. (See Drainage Board Meeting Minutes, Book 13, pages 274-278) The Drainage Board agreed to hold a public hearing on this additional work on April 25<sup>th</sup>, 2011.

I reviewed the Stony Creek / Locke Arm channel, south of 196<sup>th</sup> Street and witnessed beaver dams, sediment, and rock obstructions. The channel south of 191<sup>st</sup> Street to 186<sup>th</sup> Street has been personally maintained by owner Melvin Hair. It is in excellent condition and I do not feel any improvements are required in this area. The Stony Creek Channel from 186<sup>th</sup> Street to SR 32 was approved in the original reconstruction hearing for cleaning and removal of flow line obstructions.

The area of the proposed additional dredging is located between 191<sup>st</sup> Street and 196<sup>th</sup> Street. The clearing of trees will take place along the west side of the drain to facilitate an operation side for the equipment needed for the dredging. This will create a side for future maintenance. This clearing was previously approved as Change Order No.1 by the Drainage Board on March 14<sup>th</sup>, 2011 for \$22,000.

The proposed additional dredging will begin on the north side of  $191^{st}$ , at Station 244+90 on the proposed reconstruction plans. It will extend to the south side of  $196^{th}$  Street at Station 212 +82 on the proposed reconstruction plans. An average of 1 to 1.5 feet of sediment will be removed from the channel as well as beaver dams and other flow line obstructions. The width of the proposed channel bottom stays the same at approximately 20 feet plus or minus.

A fence gate will be installed to allow mowing of the filter strip along the Harger property. One rock line chute will be installed to reduce velocity of a side channel. Surface water pipes will be installed as needed.

Shown on the plans is the placement of a twenty foot (20') filter strip along the operational side of the drain in the agricultural land uses. This shall be considered as part of the reconstruction of the drain. The filter strip is part of the IDEM approval for this project. The filter strip shall affect the following properties:

Current Owner	Parcel
James T & Juanita T. Harger	12-07-26-00-003.000
James T & Juanita T. Harger	12-07-26-00-00-004.000

## Hydrology, Design and Environmental Permits

A watershed management plan was prepared by Christopher Burke Engineering in 2004 to 2005. This report provided recommendations to the Drainage Board for maintenance, reconstruction and flood control.

William Locke @ $211^{\text{th}}$ Street Q10 = 540 c	fs
Stony Creek (a) $186^{\text{th}}$ Street Q10 = 2,275 cf	s

O100 = 890 cfsQ100 = 2,800 cfs

The channel is designed to contain the 10 year storm frequency within the banks at all locations.

The additional reconstruction of this drain will not require acquisition of new easement for the entire length of the drain. The drain is being reconstructed in place and the existing 75 foot easement from the top of bank per IC 36-9-27-33 will be maintained. No additional easement acquisition will be required since the spoils of the project will be spread within the existing easement.

The following regulatory approval has been obtained:

- U.S. Army Crop of Engineers Regional General Permit IDNR. LRL-2009-131-sam, December 29, 2009 (Valid for 1 year)
- IDEM Section 401 Water Quality Certification No. 2009-583-29-EMP-A, December 21, 2009 (Valid for 2 years)
- IDNR Certificate of Approval, Construction in a floodway FW-25553, January 20, 2010 (Valid for 2 years)
- Soil and Water Conservation District SWPPP approval July 28, 2009

The U.S. Army Corp of Engineers permit and the IDEM permit is scheduled to expire the end of this year. Therefore, time is of the essence to finalize this work.

## Quantities & Cost Estimate

The cost estimate for this work is as follows. The unit prices were taken from the Van Horn Contract Bid for the original reconstruction project and Wetland Staking costs from Christopher Burke and Associates.

Stieet				Total
Item Description	Quantity	Unit	Unit Cost	Cost
		per		
Channel Excavation	3090	ft	7	\$21,630
Wetland				
Staking	1	LS	2,000	\$2,000
Outlet Pipes installed				
8"x 20'CMP w/animal				
guard	3	each	500	\$1,500
10"x 20'CMP w/animal				
guard	1	each	750	\$750
Sediment Basins	1	each	1,000	\$1,000
Surface Water Pipes				
installed	8	each	1,000	\$8,000
Rip				
Rap(7"to9")installed	181	ton	46	\$8,326

#### 191st Street to 196th Street

Seeding				
Channel slopes	1.1	ac	2,000	\$2,200
Filter Strip	1.5	ac	1,200	\$1,800
Ford protection	1	LS	5,000	\$5,000
Flood Gate	1	LS	2,000	\$2,000
Fence Gate	1	LS	1,500	\$1,500
Rock Lined Chute	1	LS	4,000	\$4,000
			Sub-TOTAL	\$59,706
* LS - Lump Sum		15%	Contingency	\$8,956
			TOTAL	\$68,662

• Construction to be performed by Van Horn Construction

• Wetland Staking to be performed by Christopher Burke and Associates.

### Reconstruction Assessment

The current reconstruction assessment will not increase the assessment as a result of this work.

\$ 284,615.00 Contractor Bid
\$ 19,446.00 Wetland Delineation and Staking
\$ 230.84 Regulatory Permit Costs
\$ 22,000.00 Change Order #1, clearing 191<sup>st</sup> St. to 196<sup>th</sup> St.
\$ 68,662.00 Engineers Estimate, dredging 191<sup>st</sup> St. to 196<sup>th</sup> St.

\$ 394,953.84 Total

This is less than the amount approved for Option #6 of \$ 556,151.50.

I recommend the Board consider this proposed extension to the reconstruction on April 25, 2011.

Sincerely,

Misti Kallis

Christie Kallio, P.E. Hamilton County Surveyor's Office

CK/llm

Linda K. Snelling 4908 7th B St. E Bradenton, FL 34203 Ham Co Drawage Brand Ste 188 1 Han Co Sg. APR 1 9 2011 Noblesville, In. 46060 Le: Stray Creek Dhair, docke arm SECRETARY Dead Sir n Madam: I received this notice about an assessment for this drawing ditch and my property is no 211th It & that is to seen 191" to 196th How is that to herefit me? When they pat in Sector's ditch it runs over & floods my place all the time & I don't need more water standing there. There was no phone # so I Couldn't Call & get an answer. I have a cell phone with 317 area Code 20 you could call me of epor would please. my # is 317-281-5789. Thanks for your sonsideration Linda Sulling Stony Creek-Lake Arm - 191st - 196 th This copy is from the Digital Archive of the Hamilton County Surveyor's O

## RETURNED

## OFFICE OF

## HAMILTON COUNTY DRAINAGE BOARD

Notice of Hearing to discuss the use of the unexpended funds for the extension of dredging from 191<sup>st</sup> to 196<sup>th</sup> on the **Stony Creek Drain, Locke Arm**.

Busby, Carole D Trustee 7675 W 100 N Anderson, IN 46011

The Hamilton County Drainage Board held a public hearing on May  $24^{th}$ , 2010 regarding a proposed reconstruction project known as the Stony Creek Drain / Locke Arm. Your property is listed on the schedule of assessments which will start in the spring of 2011. The original hearing held on 5/24/10 had a cost estimate of \$1,372,295.00. The Drainage Board received 11.67% objections to the project. After listening to the objections the Board adjourned the hearing to the  $26^{th}$  of July.

At the July 26<sup>th</sup> 2010 Drainage Board meeting six (6) options were presented. Option #6 was approved with a cost estimate of \$556,151.50. The assessments were reduced to the revised cost estimate. Assessments under \$100 have been certified to start collections in 2011. Assessments over \$100 have been split and the first half will start collections in 2011 and the second half will start collections in 2012. The certified assessment roll shows your parcel as follows:

Parcel	Description	Acres Benefited	Total Reconstruction Assessment	Amount to start 2011	Amount to start 2012
12-08-20-00-00-020.000	S20 T19 R6 78.71 Ac	74.03 Ac	\$5417.35	\$2708.68	\$2708.67
	Residential/Ag				

It now appears there may be funds available to do additional work in the watershed to further improve drainage. This work will not increase the cost above \$556,151.50.

A proposal to use the unexpended funds for the extension of dredging to the south, from 191<sup>st</sup> to 196<sup>th</sup> will be discussed at the April 25<sup>th</sup>, 2011 Drainage Board meeting. The meeting will be held at 9:15 A.M. in the Commissioner's Court.

For a copy of the Surveyor's Report to the Drainage Board and a copy of the map, if applicable, please go to www.hamiltoncounty.in.gov/drainageboardnotices.

## OFFICE OF HAMILTON COUNTY DRAINAGE BOARD

Notice of Hearing to discuss the use of the unexpended funds for the extension of dredging from 191<sup>st</sup> to 196<sup>th</sup> on the **Stony Creek Drain, Locke Arm**.

Busby, Carole D Trustee 7675 W 100 N Anderson, IN 46011

The Hamilton County Drainage Board held a public hearing on May 24<sup>th</sup>, 2010 regarding a proposed reconstruction project known as the Stony Creek Drain / Locke Arm. Your property is listed on the schedule of assessments which will start in the spring of 2011. The original hearing held on 5/24/10 had a cost estimate of \$1,372,295.00. The Drainage Board received 11.67% objections to the project. After listening to the objections the Board adjourned the hearing to the 26<sup>th</sup> of July.

At the July 26<sup>th</sup> 2010 Drainage Board meeting six (6) options were presented. Option #6 was approved with a cost estimate of \$556,151.50. The assessments were reduced to the revised cost estimate. Assessments under \$100 have been certified to start collections in 2011. Assessments over \$100 have been split and the first half will start collections in 2011 and the second half will start collections in 2012. The certified assessment roll shows your parcel as follows:

Parcel	Description	Acres Benefited	Total Reconstruction Assessment	Amount to start 2011	Amount to start 2012
12-08-19-00-00-006.000	S19 T19 R6 40.0 AC	40.00 Ac	\$2915.20	\$1457.60	\$1457.60
	Residential/Ag				

It now appears there may be funds available to do additional work in the watershed to further improve drainage. This work will not increase the cost above \$556,151.50.

A proposal to use the unexpended funds for the extension of dredging to the south, from 191<sup>st</sup> to 196<sup>th</sup> will be discussed at the April 25<sup>th</sup>, 2011 Drainage Board meeting. The meeting will be held at 9:15 A.M. in the Commissioner's Court.

For a copy of the Surveyor's Report to the Drainage Board and a copy of the map, if applicable, please go to <u>www.hamiltoncounty.in.gov/drainageboardnotices</u>.

# RETURNED

#### OFFICE OF

## HAMILTON COUNTY DRAINAGE BOARD

Notice of Hearing to discuss the use of the unexpended funds for the extension of dredging from 191<sup>st</sup> to 196<sup>th</sup> on the **Stony Creek Drain, Locke Arm**.

Fisher, Lydia E 14224 196th St E Noblesville, IN 46060

The Hamilton County Drainage Board held a public hearing on May 24<sup>th</sup>, 2010 regarding a proposed reconstruction project known as the Stony Creek Drain / Locke Arm. Your property is listed on the schedule of assessments which will start in the spring of 2011. The original hearing held on 5/24/10 had a cost estimate of \$1,372,295.00. The Drainage Board received 11.67% objections to the project. After listening to the objections the Board adjourned the hearing to the 26<sup>th</sup> of July.

At the July 26<sup>th</sup> 2010 Drainage Board meeting six (6) options were presented. Option #6 was approved with a cost estimate of \$556,151.50. The assessments were reduced to the revised cost estimate. Assessments under \$100 have been certified to start collections in 2011. Assessments over \$100 have been split and the first half will start collections in 2011 and the second half will start collections in 2012. The certified assessment roll shows your parcel as follows:

Parcel	Description	Acres Benefited	Total Reconstruction Assessment	Amount to start 2011	Amount to start 2012
12-07-24-00-00-015.001	S24 T19 R5 0.75 Ac	0.75 Ac	\$5.00	\$5.00	n/a
	Residential/Ag				

It now appears there may be funds available to do additional work in the watershed to further improve drainage. This work will not increase the cost above \$556,151.50.

A proposal to use the unexpended funds for the extension of dredging to the south, from 191<sup>st</sup> to 196<sup>th</sup> will be discussed at the April 25<sup>th</sup>, 2011 Drainage Board meeting. The meeting will be held at 9:15 A.M. in the Commissioner's Court.

For a copy of the Surveyor's Report to the Drainage Board and a copy of the map, if applicable, please go to <u>www.hamiltoncounty.in.gov/drainageboardnotices</u>.

# RETURNED

## OFFICE OF HAMILTON COUNTY DRAINAGE BOARD

Notice of Hearing to discuss the use of the unexpended funds for the extension of dredging from 191<sup>st</sup> to 196<sup>th</sup> on the **Stony Creek Drain, Locke Arm**.

Roudebush, Eugene F & Ruby K 1137 Wayne St Noblesville, IN 46060

The Hamilton County Drainage Board held a public hearing on May 24<sup>th</sup>, 2010 regarding a proposed reconstruction project known as the Stony Creek Drain / Locke Arm. Your property is listed on the schedule of assessments which will start in the spring of 2011. The original hearing held on 5/24/10 had a cost estimate of \$1,372,295.00. The Drainage Board received 11.67% objections to the project. After listening to the objections the Board adjourned the hearing to the 26<sup>th</sup> of July.

At the July 26<sup>th</sup> 2010 Drainage Board meeting six (6) options were presented. Option #6 was approved with a cost estimate of \$556,151.50. The assessments were reduced to the revised cost estimate. Assessments under \$100 have been certified to start collections in 2011. Assessments over \$100 have been split and the first half will start collections in 2011 and the second half will start collections in 2012. The certified assessment roll shows your parcel as follows:

Parcel	Description	Acres Benefited	Total Reconstruction Assessment	Amount to start 2011	Amount to start 2012
12-07-27-00-00-014.000	S27 T19 R5 14.0 AC	12.50 Ac	\$58.88	\$58.88	n/a
	Residential/Ag				

It now appears there may be funds available to do additional work in the watershed to further improve drainage. This work will not increase the cost above \$556,151.50.

A proposal to use the unexpended funds for the extension of dredging to the south, from 191<sup>st</sup> to 196<sup>th</sup> will be discussed at the April 25<sup>th</sup>, 2011 Drainage Board meeting. The meeting will be held at 9:15 A.M. in the Commissioner's Court.

For a copy of the Surveyor's Report to the Drainage Board and a copy of the map, if applicable, please go to <u>www.hamiltoncounty.in.gov/drainageboardnotices</u>.

## BEFORE THE HAMILTON COUNTY DRAINAGE BOARD IN THE MATTER OF

## Stony Creek Drain/Locke Arm 191<sup>st</sup> Street to 196<sup>th</sup> Street Reconstruction

#### NOTICE

To Whom It May Concern and:Busby, Carole D Trustee

Notice is hereby given of the hearing of the Hamilton County Drainage Board concerning the reconstruction of the **Stony Creek Drain/Locke Arm, 191<sup>st</sup> Street to 196<sup>th</sup> Street Reconstruction** on **April 25, 2011,** at **9:15 A.M.** in Commissioners Court, Hamilton County Judicial Center, One Hamilton County Square, Noblesville, Indiana. Construction and maintenance reports of the Surveyor and the Schedule of Assessments proposed by the Drainage Board have been filed and are available for public inspection in the office of the Hamilton County Surveyor.

Hamilton County Drainage Board

Attest:Lynette Mosbaugh

ONE TIME ONLY

STATE OF INDIANA	)		
	)	SS	BEFORE THE HAMILTON
	)		
COUNTY OF HAMILTON	)		DRAINAGE BOARD

# IN THE MATTER OF Stony Creek Drain, Locke Arm Dredging - 191<sup>st</sup> Street to 196<sup>th</sup> Street

#### NOTICE

Notice is hereby given that the Hamilton County Drainage Board at its regular meeting **April 25, 2011** adopted the reconstruction report of the Surveyor and the Amended Schedule of damages and assessments including annual assessment for periodic maintenance, finding that the costs, damages and expense of the proposed improvement would be less than the benefits which will result to the owner of lands benefited thereby.

The Board issued an order declaring the proposed improvement established. Such findings and order were marked filed and are available for inspection in the Office of the Hamilton County Surveyor.


If judicial review of the findings and order of the Board is not requested pursuant to Article VIII of the 1965 Indiana Drainage Code as amended within twenty (20) days from the date of publication of this notice, the findings and order shall become conclusive.

#### HAMILTON COUNTY DRAINAGE BOARD

BY: Steven A. Holt PRESIDENT

ATTEST: Lynette Mosbaugh SECRETARY

# Proposed Stony Creek Reconstruction 191st St to 196th St



Printing Date: 3/24/2011

Prepared By: Darren Wilson, GISP Hamilton County Surveyor's Office One Hamilton County Surveyor's Office Copyoiss from the Digital Archive of the Hamilton Sourveyor's Office; Noblesville, In 46060 317-776-8495 This (confluence of Wm Locke & Stony Creek) A No Scale