



Kenton C. Ward, CFM Surveyor of Hamilton County Thone (317) 776-8495 Fax (317) 776-9628

Suite 188 One Hamilton County Square Noblesville, Indiana 46060-2230

January 26, 2022

To: Hamilton County Drainage Board

Re: Clara Knotts Drain, Park Broadway Avenue Drain - Phase 2

Attached are the petition, plans, drainage shed map and schedule of assessments for the construction of Phase 2 of the Park Broadway Avenue Drain. The Park Broadway Avenue Drain is an arm of the Clara Knotts Regulated Drain. This drain was petitioned for by 36.8% of the property owners in the drainage shed (Hamilton County Drainage Board Minutes Book 17, Page 405). I have reviewed the petition and found it to be in proper form.

The project is located in Section 11 of Township 17 North, Range 3 East in Clay Township. The project is located entirely within the watershed of the Clara Knotts Regulated Drain and the Northridge subdivision. The project is generally located along Barbee Lane, with an extension from Barmore Avenue to College Avenue; along 103<sup>cd</sup> Street between Park Avenue and Central Avenue; along Ruckle Street from 103<sup>cd</sup> Street to the northern boundary of the Northridge subdivision; along 102<sup>cd</sup> Street between Central Avenue and Park Avenue; and along Central Avenue south of 102<sup>nd</sup> Street with an extension south to Pennsylvania Parkway.

The project will include the construction of four new arms to the Park Broadway Avenue Drain arm of the Clara Knotts Drain. The  $103^{\rm rd}$  Street and Ruckle Street Arm, the  $103^{\rm rd}$  Street and Central Avenue Arm, the  $102^{\rm nd}$  Street and Central Avenue Arm, and the Barbee Lane Arm.

I have made a personal inspection of the land described in the petition. Upon doing so, I believe that the drain is practicable, will improve the public health, benefit a public highway and be of public utility; and that the costs, damages and expenses of the proposed drain will probably be less than the benefits accruing to the owners of land likely to be benefited.

The attached plans dated April 28, 2020 were prepared by HWC Engineering for the Hamilton County Drainage Board. The Sheets being

used are G1, G2, G3, PP1, PP2, PP3, PP4, PP4.1, PP7, PP8, PP9, PP15, PP16, PP17, PP24A, PP25, PP26, PP27, PP28, PP29, DT1, DT2, DT3, EC1, EC2, EC4, EC-5, EC-6, EC7, and EC8. These sheets represent the work associated with the bids that were received by the Drainage Board on January 10, 2022.

#### Reconstruction Project

The project will provide drainage for Barbee Lane, Ruckle Street north of  $103^{\rm rd}$  Street, the north side of  $103^{\rm rd}$  Street between Central Avenue and Park Avenue, the west side of Central Avenue south of  $102^{\rm nd}$  Street, and the north side of  $102^{\rm nd}$  Street between Central Avenue and Park Avenue. The project will also drain the intersection of  $103^{\rm rd}$  Street and Central Avenue, the intersection of  $102^{\rm nd}$  Street and Central Avenue, the northwest and northeast corners of the intersection of  $102^{\rm nd}$  Street and Ruckle Street, and the southwest corner of the intersection of  $102^{\rm nd}$  Street and Park Avenue.

The project is more particularly described as follows:

#### 103rd Street and Ruckle Street Arm

Station 6+49 of	The arm starts at an existing manhole (Structure
the Park	#205) at Station 6+49 of the Park Broadway Arm of
Broadway Arm of the Clara	the Clara Knotts Drain.
Knotts Drain.	

Station 8+05	The project will proceed west with 156-LF of 36" RCP
Structure 206	and be connected to a manhole structure (Structure #206) at Station 8+05. Structure #206 will include a
	beehive casting and will be installed in the
	centerline of the roadside swale on the north side
	of 103 <sup>rd</sup> Street.

Station 8+72	The project will proceed west with 67-LF of 36" RCP
Structure 207	and be connected to a manhole structure (Structure #207) at Station 8+72. Structure #207 will include a beehive casting and will be installed in the
	centerline of the roadside swale on the north side of $103^{rd}$ Street.

Station 9+23	The project will proceed west with 51-LF of 36" RCP
Structure 208	and be connected to a manhole structure (Structure #208) at Station 9+23. Structure #208 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side
	of 103rd Street.

Station 9+53	The project will proceed west with 30-LF of 30" RCP
Structure 209	and be connected to a manhole structure (Structure #209) at Station 9+53. Structure #209 will include a beehive casting and will be installed in the

centerline of the roadside swale at the northeast corner of the intersection of 103rd Street and Ruckle Street.

Station 11+13
Structure 801

RCP and be connected to a manhole structure (Structure #801) at Station 11+13. Structure #801 will include a beehive casting and will be installed in the centerline of the roadside swale on the east side of Ruckle Street.

Structure 802

The project will proceed north with 146-LF of 15"

RCP and be connected to a manhole structure
(Structure #802) at Station 12+59. Structure #802
will include a beehive casting and will be installed in the centerline of the roadside swale on the east side of Ruckle Street.

Structure 803

The project will proceed north with 48-LF of 12" RCP and be connected to an inlet structure (Structure #803) at Station 13+07. Structure #803 will include a beehive casting and will be installed in the centerline of the roadside swale on the east side of Ruckle Street.

Station 13+53
Structure 804
The project will proceed north with 46-LF of 12" RCP and be connected to an inlet structure (Structure #804) at Station 13+53. Structure #804 will include a beehive casting and will be installed in the centerline of the roadside swale on the east side of Ruckle Street.

Station 14+65
Structure 805
The project will proceed north with 112-LF of 12"
RCP and be connected to an inlet structure
(Structure #805) at Station 14+65. Structure #805
will include a beehive casting and will be installed in the centerline of the roadside swale on the east side of Ruckle Street.

Structure 806

The project will proceed west with 36-LF of 12" RCP and be connected to an inlet structure (Structure #806) at Station 15+01. Structure #806 will include a beehive casting and will be installed in the centerline of the roadside swale on the west side of Ruckle Street.

Station 9+90 Structure #214 Structure #214 Structure #214 Station 9+90 south with 37-LF of 12" RCP and be connected to an inlet structure (Structure #214) at Station 9+90. Structure #214 will include a beehive casting and will be installed in the centerline of the roadside

swale at the southeast corner of the intersection of  $103^{\rm rd}$  Street and Ruckle Street.

Starting at Structure #801, the project will proceed west with 38-LF of 12" RCP and be connected to an inlet structure (Structure #807) at Station 11+51. Structure #807 will include a beehive casting and will be installed in the centerline of the roadside swale on the west side of Ruckle Street.

Starting at Structure #802, the project will proceed west with 27-LF of 12" RCP and be connected to an inlet structure (Structure #808) at Station 12+86.

Structure #808 will include a beehive casting and will be installed in the centerline of the roadside swale on the west side of Ruckle Street.

Starting at Structure #803, the project will proceed west with 30-LF of 12" RCP and be connected to an inlet structure (Structure #809) at Station 13+87. Structure #809 will include a beehive casting and will be installed in the centerline of the roadside swale on the west side of Ruckle Street.

#### 103rd Street and Central Avenue Arm

Station 9+93 Starting at Structure #209, the project will proceed west with 40-LF of 30" RCP and be connected to a manhole structure (Structure #210) at Station 9+93. Structure #210 will include a beehive casting and will be installed in the centerline of the roadside swale the northwest corner of the intersection of  $103^{\rm rd}$  Street and Ruckle Street.

Station 12+07
Structure 211
The project will proceed west with 214-LF of 24" RCP and be connected to a manhole structure (Structure #211) at Station 12+07. Structure #211 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side of 103rd Street.

Station 12+92
Structure 212
The project will proceed west with 85-LF of 24" RCP and be connected to a manhole structure (Structure #212) at Station 12+92. Structure #212 will include a beehive casting and will be installed in the centerline of the roadside swale at the northeast corner of the intersection of 103rd Street and Central Avenue.

Station 13+32 The project will proceed west with 40-LF of 24" PVC C905 and be connected to a manhole structure (Structure #213) at Station 13+32. Structure #213

will include a beehive casting and will be installed in the centerline of the roadside swale at the northwest corner of the intersection of  $103^{\rm rd}$  Street and Central Avenue.

Station 13+66

Structure 217

The project will proceed south with 34-LF of 12" RCP and be connected to an inlet structure (Structure #217) at Station 13+66. Structure #217 will include a beehive casting and will be installed in the centerline of the roadside swale at the southwest corner of the intersection of 103<sup>rd</sup> Street and Central Avenue.

Lateral Station 10+29

Structure 215

Starting at Structure #210, the project will proceed south with 36-LF of 12" RCP and be connected to an inlet structure (Structure #215) at Station 10+29. Structure #215 will include a beehive casting and will be installed in the centerline of the roadside swale at the southwest corner of the intersection of 103<sup>rd</sup> Street and Ruckle Street.

Lateral Station 13+28

Structure 216

Starting at Structure #212, the project will proceed south with 36-LF of 12" RCP and be connected to an inlet structure (Structure #216) at Station 13+28. Structure #216 will include a beehive casting and will be installed in the centerline of the roadside swale at the southeast corner of the intersection of 103<sup>rd</sup> Street and Central Avenue.

#### 102nd Street and Central Avenue Arm

Existing
Structure 606
Meridian
Corporate
Plaza Arm of
the Clara
Knotts Drain.

The arm starts at an existing manhole structure (Structure 606) of the Meridian Corporate Plaza Arm of the Clara Knotts Drain. An opening for the new arm shall be core drilled into the existing manhole structure at this location. This structure will be Station 0+00 of the New Arm.

Station 0+74

Structure 501

The project will proceed north with 74-LF of 30" RCP and be connected to a manhole structure (Structure #501) at Station 0+74. Structure #501 will include a beehive casting and will be installed in the centerline of the roadside swale on the west of Central Avenue.

Station 3+42 Structure 502 The project will proceed north with 268-LF of 30" RCP and be connected to a manhole structure (Structure #502) at Station 3+42. Structure #502 will include a beehive casting and will be installed

in the centerline of the roadside swale on the west side of Central Avenue.

Station 5+55 Structure 503 The project will proceed north with 213-LF of 24" RCP and be connected to a manhole structure (Structure #503) at Station 5+55. Structure #503 will include a beehive casting and will be installed in the centerline of the roadside swale at the southwest corner of the intersection of 102<sup>nd</sup> Street and Central Avenue.

Station 5+94 Structure 504 The project will proceed north with 39-LF of 24" RCP and be connected to a manhole structure (Structure #504) at Station 5+94. Structure #504 will include a beehive casting and will be installed in the centerline of the roadside swale at the northwest corner of the intersection of 102nd Street and Central Avenue.

Station 6+42 Structure 505 The project will proceed east with 48-LF of 18" RCP and be connected to a manhole structure (Structure #505) at Station 6+42. Structure #505 will include a beehive casting and will be installed in the centerline of the roadside swale at the northeast corner of the intersection of 102nd Street and Central Avenue.

Station 9+20 Structure 506 The project will proceed east with 278-LF of 18" RCP and be connected to a manhole structure (Structure #506) at Station 9+20. Structure #506 will include a beehive casting and will be installed in the centerline of the roadside swale at the northwest corner of the intersection of 102nd Street and Ruckle Street

Station 12+82 Structure 507 The project will proceed east with 362-LF of 15" RCP and be connected to an inlet structure (Structure #507) at Station 12+82. Structure #507 will include a beehive casting and will be installed in the centerline of the roadside swale at the northwest corner of the intersection of 102nd Street and Park Avenue.

Station 13+35 Structure 508 The project will proceed east with 53-LF of 12" PVC C900 and be connected to an inlet structure (Structure #508) at Station 13+35. Structure #508 will include a beehive casting and will be installed in the centerline of the roadside swale at the northeast corner of the intersection of  $102^{nd}$  Street and Park Avenue.

Lateral Station 6+81 Structure 509 Starting at Structure #505, the project will proceed south with 39-LF of 12" PVC C900 and be connected to an inlet structure (Structure #509) at Station 6+81. Structure #509 will include a beehive casting and will be installed in the centerline of the roadside swale at the southeast corner of the intersection of 102nd Street and Central Avenue.

Lateral Station 9+42 Structure 510 Starting at Structure #506, the project will proceed northeast with 22-LF of 12" RCP and be connected to a manhole structure (Structure #510) at Station 9+42. Structure #510 will include a beehive casting and will be installed in the centerline of the roadside swale at the northwest corner of the intersection of 102nd Street and Ruckle Street.

Lateral Station 9+89 Structure 511 Continuing from Structure #510, the project will proceed east with 47-LF of 12" PVC C900 and be connected to an inlet structure (Structure #511) at Station 9+89. Structure #511 will include a beehive casting and will be installed in the centerline of the roadside swale at the northeast corner of the intersection of  $102^{nd}$  Street and Ruckle Street.

Lateral Station 13+22 Structure 512 Starting at Structure #507, the project will proceed south with 40-LF of 12'' PVC C900 and be connected to an inlet structure (Structure #512) at Station 13+22. Structure #512 will include a beehive casting and will be installed in the centerline of the roadside swale at the southwest corner of the intersection of  $102^{\text{nd}}$  Street and Park Avenue.

#### Barbee Lane Arm

Existing
Structure 10
of the College
Avenue Arm of
the Clara
Knotts Drain.

The arm starts at an existing manhole structure (Structure 10) of the College Avenue Arm of the Clara Knotts Drain. The existing structure will be removed and replaced with a new manhole structure (Structure #100) at the same location. Structure #100 will include a solid casting and will be installed at Station 0+00 of the New Arm.

Station 1+70

Structure 101

The project will proceed west with 170-LF of 15" RCP and be connected to a manhole structure (Structure #101) at Station 1+70. Structure #101 will include a slotted grate casting and will be installed an existing parking area on Parcel 17-13-11-02-07-005.000.

Station 3+73

The project will proceed west with 203-LF of 15" RCP and be connected to a manhole structure (Structure

Structure 102	#102) at Station 3+73. Structure #102 will include a beehive casting and will be installed at the southeast corner of the intersection of Barmore Avenue and Barbee Lane (generally).
Station 4+84 Structure 103	The project will proceed west with 111-LF of 15" RCP and be connected to a manhole structure (Structure #103) at Station 4+84. Structure #103 will include a solid casting and will be installed in the pavement of Barbee Lane.
Station 6+70 Structure 104	The project will proceed west with 186-LF of 15" RCP and be connected to a manhole structure (Structure #104) at Station 6+70. Structure #104 will include a solid casting and will be installed in the pavement of Barbee Lane.
Station 9+27 Structure 105	The project will proceed west with 257-LF of 15" RCP and be connected to a manhole structure (Structure #105) at Station 9+27. Structure #105 will include a solid casting and will be installed in the pavement of Barbee Lane.
Station 10+41 Structure 106	The project will proceed west with 114-LF of 15" RCP and be connected to a manhole structure (Structure #106) at Station 10+41. Structure #106 will include a solid casting and will be installed in the pavement of Barbee Lane.
Station 11+32 Structure 107	The project will proceed west with 91-LF of 12" RCP and be connected to an inlet structure (Structure #107) at Station 11+32. Structure #107 will include a beehive casting and will be installed in the pavement of Barbee Lane.
Station 11+74 Structure 108	The project will proceed west with 42-LF of 12" RCP and be connected to an inlet structure (Structure #108) at Station 11+74. Structure #108 will include a beehive casting and will be installed in the pavement of Barbee Lane.
Station 11+98 Structure 109	The project will proceed northwest with 24-LF of 12" RCP and be connected to an inlet structure (Structure #109) at Station 11+98. Structure #109 will include a beehive casting and will be installed centerline of an existing swale on north side of Barbee Lane.
Lateral Station 4+97 Structure 110	Starting at Structure #103, the project will proceed north with 13-LF of 12" RCP and be connected to an inlet structure (Structure #110) at Station 4+97. Structure #110 will include a beehive casting and

will be installed in the centerline of the roadside swale on the north side of Barbee Lane.

Lateral Station 6+84 Structure 111 Starting at Structure #104, the project will proceed north with 14-LF of 12" RCP and be connected to an inlet structure (Structure #111) at Station 6+84. Structure #111 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side of Barbee Lane.

Lateral Station 9+40 Structure 112 Starting at Structure #105, the project will proceed north with 13-LF of 12" RCP and be connected to an inlet structure (Structure #112) at Station 9+40. Structure #112 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side of Barbee Lane.

Lateral Station 10+76 Structure 113 Starting at Structure #106, the project will proceed southwest with 35-LF of 12" RCP and be connected to an inlet structure (Structure #113) at Station 10+76. Structure #113 will include a beehive casting and will be installed in the centerline of the roadside swale on the south side of Barbee Lane.

Lateral Station 10+54 Structure 114 Starting at Structure #106, the project will proceed north with 13-LF of 12" RCP and be connected to an inlet structure (Structure #114) at Station 10+54. Structure #114 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side of Barbee Lane.

Lateral Station 11+45 Structure 115 Starting at Structure #107, the project will proceed north with 13-LF of 12" RCP and be connected to an inlet structure (Structure #115) at Station 11+45. Structure #115 will include a beehive casting and will be installed in the centerline of the roadside swale on the north side of Barbee Lane.

The roadside ditches at several locations will be re-graded to provide positive drainage to the new inlets. The remaining roadside ditches will not be re-graded with this project. The proposed drainage system will provide an outlet for future ditch re-grading by the City of Carmel.

The driveways of the following parcels will be affected by the project. Several driveway culverts will be replaced with the project, but these replacements are incidental to the project and the culverts will not become part of the regulated drain.

Parcel No.	Owner	Address
17-13-11-02-04- 012.000	Heston, Kerry N & Sherry L	504 Barbee Lane
17-13-11-02-04- 014.000	Thomas, John H Jr & Rachel Ann	578 Barbee Lane
17-13-11-02-04- 016.000	Reeves, Stephen J & Lisa K	580 Barbee Lane
17-13-11-02-04- 021.000	Allen, Beverley	590 Barbee Lane
17-13-11-02-04- 023.000	Craig, Benny & Susan	602 Barbee Lane
17-13-11-02-04- 026.000	McMillan, Lawrence J & Peggy S	606 Barbee Lane
17-13-11-02-04- 029.000	Hendricks, Douglas W & Denise jt	612 Barbee Lane
17-13-11-02-07- 005.000	Contour Acquisitions LLC	10450 North College Avenue
17-13-11-02-11- 014.000	Cole, Christopher Brian & Heather	10301 Ruckle Street North
17-13-11-02-11- 033.000	Devilbiss, David S & Therese P	10301 North Central Avenue
17-13-11-02-11- 016.000	Martinez, Carlos Gustavo Valiente Sr & Maria Fatima Marin Villa h&w	10305 Ruckle Street North
17-13-11-02-11- 018.000	Webster, Kristina M	10309 Ruckle Street North
17-13-11-02-11- 020.000	Salazar, Katheryn Brooke	10315 Ruckle Street North
17-13-11-02-11- 022.000	Lopez, Antonio	10345 Ruckle Street North
17-13-11-02-11- 028.000	Nickless, Gary D & Rebecca D	10340 Ruckle Street North
17-13-11-04-02- 027.000	Klink, Gregory W & Pamela S	10120 North Central Avenue

Page 10 of 19

17-13-11-04-02- 021.000	Johnson, Jeffrey L & Beverly A	10144 North Central Avenue
17-13-11-04-02- 024.000	Crawford, Norman E & Barbara G Trustees of Norman E & Barabara G Crawford Lvg Trust	10130 North Central Avenue
17-13-11-02-10- 030.000	Perry, Kristen M	520 East 102nd Street

#### **Permits**

Permits for this project will include approval from the City of Carmel for any roadway closures and roadway lane restrictions.

#### Construction Costs

The Clara Knotts Park Broadway Avenue Drain, Phase 2 project was approved for letting at the November 22, 2021 meeting of the Drainage Board (Hamilton County Drainage Board Meeting Minutes, Book 20, Page 236). The bid included a Base Bid and one Alternate Bid. The Alternate Bid was for trenchless installation of the piping between the existing Structure 606 of the Meridian Corporate Plaza Arm and Structure 501 of this project.

One addendum was issued. The addendum issued the most current Common Construction Wage Rate determination prior to receiving bids.

One bid was received from Morphey Construction on January 10, 2022. The Base Bid amount was \$1,440,000.00. The Alternate Bid amount was \$111,000.00.

The Alternate Bid will not be accepted due to the cost.

From the received bid, the construction cost of the project is estimated to be \$1,656,000.00. This cost includes a 15% contingency.

An outline of the detailed construction costs are as follows:

Detail:	Detailed Construction Cost Estimate						
Line Item	Item Description	Unit	Quantity	Unit Cost	Total Cost		
BB−1	Tree removal	EA	4	\$1,400.00	\$5,600.00		
BB-2	Culvert removal	EA	1	\$1,400.00	\$1,400.00		
BB-3	Asphalt Driveway removal and repair per detail M-1	EA	9	\$3,200.00	\$28,800.00		
вв-4	Concrete Driveway removal and repair per detail M-2	EA	1.	\$3,000.00	\$3,000.00		

Page 11 of 19

BB-5	Driveway Remove and Repair per Detail 10- 24; 12" PCCP Cap Only	EA	3	\$1,500.00	\$4,500.00
BB-6	Parking area removal and repair per Detail 10-24	LF	240	\$45.00	\$10,800.00
BB-7	Roadway removal and repair per Detail 10-24	LF	440	\$41.00	\$18,040.00
BB-8	Roadway Removal and Repair per Detail 10- 24; 12" PCCP Cap Only	LF	796	\$100.00	\$79,600.00
BB-9	Sidewalk removal and repair	EA	3	\$3,100.00	\$9,300.00
BB-10	ADA Ramp Removal and Repair	EA	3	\$2,700.00	\$8,100.00
BB-11	1.5" Surface Milling	SYS	1589	\$8.00	\$12,712.00
BB-12	Inlet Remove [21, 24, 27, 29, 53, 56, 20, 25, 26, 30]	EA	10	\$450.00	\$4,500.00
BB-13	Manhole Remove [3, 10, 22, 49]	EA	4	\$500.00	\$2,000.00
BB-14	Erosion Control	LS	1	\$82,555.00	\$82,555.00
BB-15	Maintenance of Traffic	LS	1	\$45,000.00	\$45,000.00
BB-16	Inlet D-22 with casting [107, 108, 109, 110, 111, 112, 113, 114, 115, 214, 215, 216, 217, 507, 508, 509, 511, 512, 803, 804, 805, 806, 807, 808, 809]	EA	25	\$2,800.00	\$70,000.00
BB-17	Manhole D-20, 48" Diameter with casting [102, 103, 104, 105, 501, 502, 503, 504, 505, 506, 510]	EA	11	\$6,900.00	\$75,900.00
BB-18	Manhole D-21, 60" Diameter with casting [100, 106, 206, 207, 211, 801, 802]	EA	7	\$7,100.00	\$49,700.00
BB-19	Manhole D-21, 60" Diameter with casting and Stub Pipes [209, 210, 212, 213]	EA	4	\$7,100.00	\$28,400.00
BB-20	Manhole D-21, 96" Diameter with casting [101, 208, 500]	EA	3	\$17,000.00	\$51,000.00
BB-21	Pipe, Type 2, Circular, 12" PVC C900 with Flowable Fill Backfill	LF	123	\$150.00	\$18,450.00

BB-22	Pipe, Type 2, Circular, 12" PVC C900 with General Backfill	LF	56	\$115.00	\$6,440.00
BB-23	Pipe, Type 2, Circular, 12" RCP with Flowable Fill Backfill	LF	496	\$120.00	\$59,520.00
BB-24	Pipe, Type 2, Circular, 12" RCP with General Backfill	LF	230	\$75.00	\$17,250.00
BB-25	Pipe, Type 2, Circular, 12" RCP with Granular Backfill	LF	34	\$100.00	\$3,400.00
BB-26	Pipe, Type 2, Circular, 12" RCP with Granular Backfill, Stub Pipe	LF	32	\$160.00	\$5,120.00
BB-27	Pipe, Type 2, Circular, 15" RCP with Flowable Fill Backfill	LF	928	\$210.00	\$194,880.00
BB-28	Pipe, Type 2, Circular, 15" RCP with General Backfill	LF	750	\$100.00	\$75,000.00
BB-29	Pipe, Type 2, Circular, 15" RCP with Granular Backfill	LF	31	\$165.00	\$5,115.00
BB-30	Pipe, Type 2, Circular, 18" RCP with Flowable Fill Backfill	LF	48	\$235.00	\$11,280.00
BB-31	Pipe, Type 2, Circular, 18" RCP with General Backfill	LF	242	\$115.00	\$27,830.00
BB-32	Pipe, Type 2, Circular, 18" RCP with Granular Backfill	LF	36	\$180.00	\$6,480.00
BB-33	Pipe, Type 2, Circular, 24" PVC C905 with Flowable Fill Backfill	LF	40	\$400.00	\$16,000.00
BB-34	Pipe, Type 2, Circular, 24" RCP with Flowable Fill Backfill	LF	39	\$270.00	\$10,530.00
BB-35	Pipe, Type 2, Circular, 24" RCP with General Backfill	LF	482	\$150.00	\$72,300.00
BB-36	Pipe, Type 2, Circular, 24" RCP with Granular Backfill	LF	30	\$215.00	\$6,450.00
BB-37	Pipe, Type 2, Circular, 30" RCP with Flowable Fill Backfill	LF	40	\$500.00	\$20,000.00
BB-38	Pipe, Type 2, Circular, 30" RCP with General Backfill	LF	328	\$380.00	\$124,640.00
BB-39	Pipe, Type 2, Circular, 30" RCP with Granular Backfill	LF	44	\$370.00	\$16,280.00

BB-40	Pipe, Type 2, Circular, 36" RCP with General Backfill	LF	254	\$215.00	\$54,610.00
BB-41	Pipe, Type 2, Circular, 36" RCP with Granular Backfill	LF	20	\$300.00	\$6,000.00
BB-42	Concrete Cradle	EA	3	\$750.00	\$2,250.00
BB-43	6" HDPE Perforated SSD with stone backfill	LF	80	\$70.00	\$5,600.00
BB-44	SSD Riser	EA	4	\$900.00	\$3,600.00
BB-45	1.5" Resurfacing	SYS	1589	\$12.00	\$19,068.00
BB-46	Grading at Inlets	EA	20	\$170.00	\$3,400.00
BB-47	Swale Regrading at Inlets	EA	6	\$600.00	\$3,600.00
BB-48	Proposed Drive Culvert	EA	7	\$2,000.00	\$14,000.00
BB-49	Gas service relocation	EA	2	\$2,500.00	\$5,000.00
BB-50	Sanitary lateral Relocation	EA	4	\$3,500.00	\$14,000.00
BB-51	Water service relocation	EA	6	\$3,500.00	\$21,000.00
	Base Bid Construction Costs				

#### **Easements**

The project will be installed within the existing rights-of-way of  $103^{\rm rd}$  Street,  $102^{\rm nd}$  Street, Park Avenue, College Avenue, Central Avenue, Ruckle Street, and Pennsylvania Parkway.

The acquisition of additional permanent regulated drain easement is necessary for the construction of the project. Easement must be acquired from the following parcels. The estimated easement acquisitions including appraisals is \$247,000.00.

Parcel Number	Deeded Owner	Easement Area (acres)
17-13-11-00-00- 007.000	Hughes, Lawrence K & Mary Beth Trustees Lawrence K Hughes Living Trust, et. al	0.01
17-13-11-02-04- 021.000	Allen, Beverley	0.087

Page 14 of 19

17-13-11-02-04- 012.000	Heston, Kerry N & Sherry L	0.052
17-13-11-02-04- 029.000	Hendricks, Douglas W & Denise	0.075
17-13-11-02-04- 016.000	Reeves, Stephen J & Lisa K	0.082
17-13-11-02-07- 009.000	Swiss Capital Enterprises LLC	0.097
17-13-11-02-04- 023.000	Craig, Benny & Susan	0.083
17-13-11-02-04- 030.000	Hayes, Sean	0.073
17-13-11-02-04- 026.000	McMillan, Lawrence J & Peggy S	0.076
17-13-11-02-04- 014.000	Thomas, John H Jr & Rachel Ann	0.082
17-13-11-02-07- 005.000	Contour Acquisitions LLC	0.162

#### Changes to the Drain

The drain constructed with this project will consist of the following:

Inlet Structures	25
Manhole Structures	25
12" PVC C900 Tile	179-feet
12" RCP Tile	760-feet
15" RCP Tile	1,709-feet
18" RCP Tile	326-feet
24" PVC C905 Tile	40-feet
24" RCP Tile	551-feet
30" RCP Tile	412-feet
36" RCP Tile	274-feet

Page 15 of 19

The total length of the new drain will be 4,251-feet.

The project includes the installation of 4, 20-foot lengths of sub-surface drain pipes (a total of 80-feet per Line Item BB-43) for the benefit of draining water from the soil under roadside swales that drain into Structures 209, 210, 212, and 213 from the north. The project also includes the installation of 4, 8-foot stub pipes (a total of 32-feet per Line Item BB-26) for possible future piping connections on the north side of Structures 209, 210, 212, and 213. These installations are ancillary and will not be included in the regulated drain inventory. As such, the table above does not reflect these pipe lengths and these pipes lengths are not included in the total length of the new drain noted above.

#### Total Project Costs

The total project costs are outlined below. The cost for a remote camera inspection of an existing tile by Fluid Waste Services, Inc. [Reference Invoice WO-19180 dated 3/17/2017 in the amount of \$431.25] during the design of this project is included in the total cost of the project. The cost of the project will include professional surveying services. These services will include construction staking, periodic grade checks, as-built survey, and as-built drawings. The cost for easement acquisition, and the professional services associated with the acquisitions, is included in the total project cost.

Total Project	Costs
Construction Cost	\$1,440,000.00
15% Construction Contingency	\$216,000.00
Fluid Waste Services, Inc.	\$431.25
Professional Survey Services	\$82,000.00
Appraisals [11-easements @ \$3,500 per easement]	\$38,500.00
Easement Acquisition	\$208,500.00
Total Project Cost	\$1,985,431.25

#### Project Funding

Per IC-36-9-27-71, the costs for the section of the drain crossing  $103^{\rm rd}$  Street,  $102^{\rm nd}$  Street, Barbee Lane, Central Avenue, Ruckle Street, Park Avenue, and College Avenue shall be assessed to the City of Carmel. These costs are as follows:

Line Item No.	Description	Unit	Quant ity	Unit Price	Total Cost
BB-7	Roadway removal and repair per Detail 10-24	LF	440	\$41.00	\$18,040.00
BB-8	Roadway Removal and Repair per Detail 10-24; 12" PCCP Cap Only	LF	796	\$100.00	\$79,600.00
BB-11	1.5" Surface Milling	SYS	1589	\$8.00	\$12,712.00
вв-16	Inlet D-22 with casting [107, 108, 113, 214, 215, 216, 217, 507, 508, 509, 511, 512, 803, 805, 806, 807, 808, 809]	EA	18	\$2,800.00	\$50,400.00
вв-17	Manhole D-20, 48" Diameter with casting [102, 103, 104, 105, 503, 504, 505, 506, 510]	EA	9	\$6,900.00	\$62,100.00
BB-18	Manhole D-21, 60" Diameter with casting [100, 106, 801, 802]	EA	4	\$7,100.00	\$28,400.00
BB-19	Manhole D-21, 60" Diameter with casting and Stub Pipes [209, 210, 212, 213]	EA	4	\$7,100.00	\$28,400.00
BB-21	Pipe, Type 2, Circular, 12" PVC C900 with Flowable Fill Backfill	LF	123	\$150.00	\$18,450.00
BB-22	Pipe, Type 2, Circular, 12" PVC C900 with General Backfill	LF	56	\$115.00	\$6,440.00
BB-23	Pipe, Type 2, Circular, 12" RCP with Flowable Fill Backfill	LF	425	\$120.00	\$51,000.00
BB-24	Pipe, Type 2, Circular, 12" RCP with General Backfill	LF	7	\$75.00	\$525.00
BB-25	Pipe, Type 2, Circular, 12" RCP with Granular Backfill	LF	10	\$100.00	\$1,000.00
BB-27	Pipe, Type 2, Circular, 15" RCP with Flowable Fill Backfill	LF	693	\$210.00	\$145,530.00
BB-28	Pipe, Type 2, Circular, 15" RCP with General Backfill	ĻF	20	\$100.00	\$2,000.00

вв-29	Pipe, Type 2, Circular, 15" RCP with Granular Backfill	LF	5	\$165.00	\$825.00
BB-30	Pipe, Type 2, Circular, 18" RCP with Flowable Fill Backfill	LF	48	\$235.00	\$11,280.00
вв-33	Pipe, Type 2, Circular, 24" PVC C905 with Flowable Fill Backfill	LF	40	\$400.00	\$16,000.00
BB-34	Pipe, Type 2, Circular, 24" RCP with Flowable Fill Backfill	LF	39	\$270.00	\$10,530.00
BB-37	Pipe, Type 2, Circular, 30" RCP with Flowable Fill Backfill	LF	40	\$500.00	\$20,000.00
BB-45	1.5" Resurfacing	SYS	1589	\$12.00	\$19,068.00
City of Carmel Construction Costs					\$582,300.00
15% Contingency					\$87,345.00
	Total City of Carmel Costs				

A portion of the project will be funded by the Coronavirus State and Federal Fiscal Recovery Funds of the American Rescue Plan. As of the date of this report, the first round of funds from this program is available. The portion of the project cost to be funded from these ARPA funds is \$1,315,355.00. The total amount of the ARPA funds allocated for this project is \$1,447,720.00; leaving a balance of \$132,365.00 available from the ARPA funds that could be applied to any project over runs.

Parcels benefitted by this Drain are currently assessed for the Clara Knotts Drain. Therefore, no changes in the current maintenance assessment shall be required. The maintenance fund for the Clara Knotts drain presently receives \$17,878.66 per year. The \$431.25 paid to Fluid Waste from General Drain Improvement Fund on April 11, 2017 for camera work north of  $103^{\rm rd}$  from Ruckel to Centual Avenue shall be reimbursed from the Clara Knotts maintenance fund.

The costs for this project will be paid from the following sources:

City of Carmel \$ 669,645.00

Maintenance Fund \$ 431.25

ARPA Funding \$1,315,355.00

Total: \$1,985,431.25

I have reviewed the drainage shed for the Clara Knotts Drain and upon considering each parcel individually, I believe each parcel within the sub-area of the drainage shed will have equal benefits, by land use, as provided by the drain. I believe that no damages will result to landowners by construction of this drain.

I believe this proposed drain meets the requirements for Urban Drain Classification as set forth in IC-36-9-27-67 to 69. Therefore, this drain shall be designated as an urban drain.

I recommend that the Board set a hearing for this proposal for March 28,2022.

Sincerely

Kenton C. Ward, CFM

Hamilton County Surveyor's Office

KCW/pll

# F-I L E C

RENTER?

OFFICE OF HAMILTON COUNTY SURVEYOR
To: Hamilton C

To: Hamilton County Drainage Board

Date: 5-12-2015

Re: CLARA KNOTTS Drain

MICHAEL GOODE, 10340 BRONDWAY (Here-in-after "Petitioner"), hereby petitions the Hamilton County Drainage Board under IC 36-9-27-66 for an arm to be installed to the Chara Knows Drain in order to serve the property of the petitioner. The petitioner, in support of said petition, advises the Board that:

- 1. The CLARA KNOTTS Drain is presently on a maintenance program and that land of the petitioner is assessed as benefited by the maintenance of the regulated drain
- 2. There is no known adequate open or tiled drain connecting the land of the petitioner with the regulated drain;
- 3. The waters from the petitioners land flow over or through land owned by others to reach the regulated drain;
- 4. The legal description of lands through which the new regulated drain will run along with the parcel numbers, name and address of each owner of that land is shown on Exhibit "A" which is attached;
- 5. The general route of the proposed new regulated drain and method of construction is shown on Exhibit "B" which is attached.

6. Petitioner agrees to pay all legal and construction costs involved with the construction of the proposed new regulated drain. DOES NOT APPLY, PER ANDREW CONOVER THRE 15

Signed

Muran Room

MICHARI GOODE

M


Adobe PDF Fillable Form

CLARA	KNUTTS	Drain Petition
		=: 0 00:10101

Sgnature	Printed Name	Printed Address
Male Johnson	Michael Timmons Ryan Clarke	10330 N. PARK AVE 10324 N Broadway St.

Adobe PDF Fillable Form

### Clara Knotts Petition




July 31, 2015

<all other values> CLOSED DRAIN -- SSD

⊕ MUNICIPAL MANHOLE --- MUNICIPAL DRAIN — Regulated Drains Waterways

Regulated Drains Text — OPEN DRAIN — Regulated Drains Drainage Pool



# Figure 1: Clara Knotts Drain Stormwater Improvements



Hamilton County



103 nd &
Bruadoway





OFFICE OF HAMILTON COUNTY SURVEYOR Date: 5-12-2015 Hamilton County Drainage Board To: CLARA KNOTTS Re: OFFICE OF HAMILTON COUNTY SURVEYOR MICHAEL GOUDE, 10340 BROADWAY (Here-in-after "Petitioner"), hereby petitions the Hamilton County Drainage Board under IC 36-9-27-66 for an arm to be installed to the Chara Knows Drain in order to serve the property of the petitioner. The petitioner, in support of said petition, advises the Board that: 1. The CLARA KNOTTS Drain is presently on a maintenance program and that land of the petitioner is assessed as benefited by the maintenance of the regulated drain 2. There is no known adequate open or tiled drain connecting the land of the petitioner with the regulated drain; 3. The waters from the petitioners land flow over or through land owned by others to reach the regulated drain; 4. The legal description of lands through which the new regulated drain will run along with the parcel numbers, name and address of each owner of that land is shown on Exhibit "A" which is attached; 5. The general route of the proposed new regulated drain and method of construction is shown on Exhibit "B" which is attached. 6. Petitioner agrees to pay all legal and construction costs involved with the construction of DOES NOT APPLY, PER ANDREW CONOVER JUNE 16 15 the proposed new regulated drain. Printed Signed 10340 GOODE BRUADWA 16304 BRUADUR BRUADWAY 10318 Rester? BAUADW PARK 10309

This copy printed from Digital Archive of the Hamilton County Surveyor's Office; One Hamilton Co. Square, Ste., Noblesville, In 46060

Drain Petition

FILED

JUN 23 2017

Sgnature

Printed Name

Printed Address

TIGE OF HAMILTON COUNTY SURVEYOR

10330 N, PARK AUE. N Broadnay St. Broadway St. 1020 5 RUCKLE ST. 10146 RUCKIC St. Jacqueline longs 10237 N. Park Ave 10236 N. Pank Ave

Signature	Printed Name	Printed Address	3	
Stuf	Cupp	10210	Bronoway	4628
Bettell	Blatbea	10/91	520 ADWAY	46286°
- 1				
			,	
8				<u></u>
			JUN 2.3	E D
			OFFICE OF HAMILTON 6	
4				
9				
	,		· · · · · · · · · · · · · · · · · · ·	
			<u> </u>	



To: Hamilton County Drainage Board

Re: In the ma	tter of the	Clara Knotts	_Drain Petition	OF HAMILTON C	OUNTY SURVEYOR
Comes nov 9-27, for the r	w the undersigned increconstruction of the	dividuals, who petition the	e Hamilton County ed drain. The under	Drainage Board, per IC 3	36-
	ey are owners of ten p ected by the drain.	ercent (10%) in acreage	or more of land are	a alleged by the petition	to be
2. Tha	t as property owners	within the drainage shed	, they are qualified	petitioners.	
3. Tha	t they now desire tha	t a regulated drain be rec	onstructed in	Clay Township.	
mac area	de a part hereof, and i	marked Exhibit "A", whi	ch area of land invo	drainage are attached he lived in the proposed drai a east, Hamilton Cou	nage
5. Tha	at the proposed recons	struction consists of Exte	ending storm sewer to	serve area along 103rd, Pa	ark,
Broa	adway, Ruckle including	g 102nd, Central and New	Jersey.		
					·
imp		e Petitioner, the costs, da s than the benefits which			
		e Petitioner, the proposed; and be of public utility.		improve the public health	1;
	at Petitioners shall pa ition is dismissed.	y the cost of notice and a	ll legal costs includ	ing engineering expense	if the
	itioners shall post a b provement is not estal		ne cost of notice and	d all legal costs in the cas	e the
Signature I seed	11/1/	ed Name ed I Hank Nova Autr	Printed Address	N. Ruckle S	Tuelphe In
Jua	n Join	2 Joan Goi	ns 10330	Rucklest	
Rebecc	a Nichley F	Labecca Nickle	51 10345	Ruchele 5t	<u>.</u>
Stor Cl	In Ste	ghen Buckler	10346 R	include St.	
Michael	Ddull Mi	chael Schull	10399 R	Luckle St.	
afer	Eyen Ad	TAMES LO 180	210345	RULKLE. ST.	<b>-</b>
Podric	ie Brea Cap.	kr Patricia SI	hea Capent	Rulklegt. er 10305 R	welle St.
8	· · · · · · · · · · · · · · · · · · ·				
8		<u> </u>	<del>-</del> -		
1					

To: Hamilton County Drai	_		JUN 2.3 2017
Re: In the matter of the	Clara Knotts gned individuals, who petition the	Drain Petition	OF HAMILTON COUNT
Comes now the undersi 9-27, for the reconstruction	gned individuals, who petition the of the above referenced regulated	Hamilton County Draina I drain. The undersigned	ge Board, per IC 36- believe the following:
1. They are owners affected by the d	of ten percent (10%) in acreage or rain.	more of land area allege	ed by the petition to be
2. That as property	owners within the drainage shed,	hey are qualified petition	ers.
3. That they now do	esire that a regulated drain be reco	nstructed in Clay	Township.
made a part here	Idress of each owner affected by the of, and marked Exhibit "A", which section17, township17	area of land involved in	the proposed drainage
5. That the propose	ed reconstruction consists of extend	ling the drain to provide dra	inage for Central Avenue,
103rd Street, 102r	nd Street, Ruckle Avenue, New Jersey	Street, Broadway Avenue,	and Park Avenue.
improvement wi benefited thereby		rill result to the owners of	the land to be
	on of the Petitioner, the proposed in highway; and be of public utility.	-	e the public health;
8. That Petitioners petition is dismis	shall pay the cost of notice and all ssed.	legal costs including engi	neering expense if the
9. Petitioners shall improvement is a	post a bond, if required, to pay the not established.	cost of notice and all lega	al costs in the case the
Signature	Printed Name	Printed Address	
N. Chillia	David S. DeVilbiss	10301 Central Avenue, Inc	dianapolis IN 46280
Theres Polities	Therese P. DeVilbiss	10301 Central Avenue, Inc	dianapolis IN 46280
Beurleg Heider	Beverly Heider	10321 Central	Ave Indianapolis
Massarich	J.D. DIEDERICH	10328 Central 1	Ave, Indpls 1N 46280
Welly Namon	Audrey Charpman	10355 Central	-Ae Indpisim
The Disto	Teal MANIN	10236 Central	Fiction 16280
Bobbinul.	Bobbie Miller	10226 CENTRAL	IN DPLS 46280
Elda Miller	Elda Miller	10226 CENTRAL	INDPLS 46280
Instarrin	Mark Garrison	10223 Central A	lue Indpls 46280
Thay ri	SHARON Criss	10219 Central	Aur Inelals 46280
AMA/M	Mate Williams	10201 CENTIAl	AV, Inde/s 46280
220°	W.R. Rice	407 E. 102 Nd 8	st INdy 46180
Signel	Sonja mic arrel	1027 N. New Ja	25ey Indps 4,280

STATE OF INDIANA )
) ss:
COUNTY OF HAMILTON )

BEFORE THE HAMILTON COUNTY DRAINAGE BOARD NOBLESVILLE, INDIANA

IN THE MATTER OF THE RECONSTRUCTION OF THE

Clara Knotts Drain, Park Broadway Avenue Drain - Phase 2

#### FINDINGS AND ORDER FOR RECONSTRUCTION

The matter of the proposed Reconstruction of the Clara Knotts Drain, Park Broadway Avenue Drain - Phase 2 Reconstruction came before the Hamilton County Drainage Board for hearing on March 28, 2022, on the Reconstruction Report consisting of the report and the Schedule of Damages and Assessments. The Board also received and considered the written objection of an owner of certain lands affected by the proposed Reconstruction, said owner being:

Evidence was heard on the Reconstruction Report and on the aforementioned objections.

The Board, having considered the evidence and objections, and, upon motion duly made, seconded and unanimously carried, did find and determine that the costs, damages and expenses of the proposed Reconstruction will be less than the benefits accruing to the owners of all land benefited by the Reconstruction.

The Board having considered the evidence and objections, upon motion duly made, seconded and unanimously carried, did adopt the Schedule of Assessments as proposed, subject to amendment after inspection of the subject drain as it relates to the lands of any owners which may have been erroneously included or omitted from the Schedule of Assessments.

The Board further finds that it has jurisdiction of these proceedings and that all required notices have been duly given or published as required by law.

Wherefore, it is ORDERED, that the proposed Reconstruction of the Clara Knotts Drain, Park Broadway Avenue Drain - Phase 2
Reconstruction be and is hereby declared established.

Thereafter, the Board made inspection for the purpose of determining whether or not the lands of any owners had been erroneously included or excluded from the Schedule of Assessments. The Board finds on the basis of the reports and findings at this hearing as follows:

on county drainage board

PRESIDENT

Member

Member

ATTEST:

This copy printed from Digital Archive of the Hamilton County Surveyor's Office; One Hamilton Co. Square, Ste., Noblesville, In 46060

Returned-03/03/2022

# OFFICE OF HAMILTON COUNTY DRAINAGE BOARD February 25, 2022

Notice of Hearing on Reconstruction & Schedule of Assessments and Damages on the Clara Knotts Drain, Park Broadway Avenue Drain – Phase 2.

CAMNA LLC 10145 N Central Ave Carmel, IN 46280 Under the Indiana Drainage Code, all land which drains directly, or indirectly, may be assessed for either maintenance cost or reconstruction cost within the drain. In making the calculation for each parcel, the Drainage Board must calculate the percentage of the cost attributable to each parcel of land benefitted. The Drainage Board has received a reconstruction report and schedule of assessments which affects your land. The purpose of the reconstruction project is to perform work which will substantially improve the drainage for the entire watershed served by the drain.

You are hereby notified that the reconstruction report of the County Surveyor and the schedule of assessments made by the Drainage Board have been filed and are available for public inspection in the office of the County Surveyor. The chart below contains your proposed assessment and your percentage of the total reconstruction assessment.

The reconstruction report of the Surveyor and schedule of damages and benefits as determined by the Drainage Board for the proposed improvement known as the Clara Knotts Drain, Park Broadway Avenue Drain — Phase 2 have been filed and are available for inspection in the office of the County Surveyor. The schedule of assessments shows the following lands in your name are affected as follows. This assessment is not a charge for services associated with regulating the quality of storm water within your city or town.

Description of Land	Acres	Damages	Reconst.	% of	Maint.
17-13-11-04-03-041.000	Benefited	Damages	Assmt.	Total	Assmt.
S11 T17 R3 Northridge/Carmel Clay Lot Pt	*	Zero	*	*	*
255,253,254					
* To be paid by ARPA funds (American Rescue	Plan) and City of	Carmel,			
* No change in current maintenance assessment r					

The hearing on the Surveyor's reconstruction report and on the schedules of damages and assessments are set for hearing at 9:00 A.M. on March 28, 2022 in the Commissioner's Court. The law provides that objections must be written and filed not less than 5 days before the date of the hearing. Objections may be for causes as specified by law and which are available at the Surveyor's Office. Written evidence in support of objections may be filed. The failure to file objections constitutes a waiver of your right to thereafter object, either before the Board or in court on such causes, to any final action of the Board. On or before the day of the hearing before the Board, the Surveyor shall and any owner of affected lands may cause written evidence to be filed in support of or in rebuttal to any filed objections.

HAMILTON COUNTY DRAINAGE BOARD One Hamilton County Square, Ste. 188 Noblesville, IN 46060-2230

For a copy of the Surveyor's Report to the Drainage Board and a copy of the map, if applicable, please go to www.hamiltoncounty.in.gov/drainageboardnotices.

## BEFORE THE HAMILTON COUNTY DRAINAGE BOARD IN THE MATTER OF

## Clara Knotts Drain, Park Broadway Avenue Drain Phase 2

NOTICE

То	Whom	Ιt	May	Concern	and:	CAMNA,	LLC		 

Notice is hereby given of the hearing of the Hamilton County Drainage Board concerning the reconstruction of the Clara Knotts Drain, Park Broadway Avenue Drain Phase 2 on March 28, 2022 at 9:00 A.M. in Commissioners Court at the Historic Courthouse, 2<sup>nd</sup> Floor Historic Courtroom at 33 North 9<sup>th</sup> Street, Noblesville, Indiana. Construction and maintenance reports of the Surveyor and the Schedule of Assessments proposed by the Drainage Board have been filed and are available for public inspection in the office of the Hamilton County Surveyor.

Hamilton County Drainage Board

Attest: Lynette Mosbaugh

ONE TIME ONLY

STATE	OF	INDIANA	)				**************************************
			)	SS	BEFORE	T.HE	HAMILTON
			)				
COUNTY	OF	HAMILTON	)		DRAINAC	SE BO	DARD

IN THE MATTER OF Clara Knotts Drain, Park Broadway Avenue Drain, Phase 2

#### NOTICE

Notice is hereby given that the Hamilton County Drainage Board at its regular meeting March 28, 2022 adopted the reconstruction report of the Surveyor and the Amended Schedule of damages and assessments including annual assessment for periodic maintenance, finding that the costs, damages and expense of the proposed improvement would be less than the benefits which will result to the owner of lands benefited thereby.

The Board issued an order declaring the proposed improvement established. Such findings and order were marked filed and are available for inspection in the Office of the Hamilton County Surveyor.

If judicial review of the findings and order of the Board is not requested pursuant to Article VIII of the 1965 Indiana Drainage Code as amended within twenty (20) days from the date of publication of this notice, the findings and order shall become conclusive.

HAMILTON COUNTY DRAINAGE BOARD

BY: Christine Altman
PRESIDENT

ATTEST: Lynette Mosbaugh
SECRETARY